

OFFICE: 843-559-5649 Fax: 843-557-0826 E-mail:info@riversidedockbuilders.com

## RIVERSIDE DOCK & DECK CONSTRUCTION, INC.

## **Our Seawall Specifications**

Wood Seawall 4' or Less

Pilings are 2.5 Marine Treated and are placed on 8' Centers with 50% penetrations.

Whalers are 2.5 Marine Treated 4" by 6" Placed on 2' Centers. Install horizontally attached Piling to Piling and Bolted Together.

Sheet Pile is 2.5 Marine Treated 2" by 8" Sloppy V Grove. Installed Verticality to 50% Penetrations and nailed to Whalers with 16 penny Stainless Steel Nails.

Filter Cloth is placed on Land Side of wall and Attached with Stainless Steel Nails.

Tie Backs will be placed when needed at each pile set with either cables or Galvanized Sag Road Attached to a Dead Man or Concrete Footings.

2" x 8" Cap will be placed on Top of Wall.